

3-16-19W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- ANSCHUTZ DRILLING CO., INC.
Farm- Seelye No.1

SEC. 3 T. 16 R. 19W
NW SW SE

Total Depth. 3655'
Comm. 1-22-56 Comp. 3-3-56
Shot or Treated.
Contractor.
Issued. 3-31-56

County Rush

KANSAS



CASING:
8 5/8" 233' cem w/1.75 sx

Elevation. 2043' RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay	60
shale	190
shale & shells	244
shale	683
sand	913
shale	950
shale & shells	1240
anhydrite	1277
shale & shells	1360
shale, shell & red bed	1595
shale	1725
shale & salt	1860
shale	1919
shale & lime	2035
shale & lime	2165
lime & shale	2255
lime & shale	2365
shale & lime	2470
shale & lime strks	2500
shale	2570
shale & shells	2715
shale & lime strks	2845
shale & lime	3185
lime & shale	3372
lime	3410
lime & shale	3468
lime	3493
cherty lime & shale	3503
lime	3549
lime, shale & chert	3595
shale, chert, lime & sand	3617
chert, shale, sand	3628
Reagan sand	3655 RTD
Total Depth	

Tops: Scout	
Dakota	683
Heebner	3284
Lansing	3327
Base Kansas City	3557
Conglomerate	3605
Reagan	3622