

36-28-16E

LOG

Company Kelt Oil & Gas Lease Folger Well No. KCAF-10

SQUIRREL SANDSTONE

<u>Depth Interval, Feet</u>	<u>Description</u>
724.0 - 724.5	Shale and sandstone, gray and brown, alternate layers.
724.5 - 725.0	Shale, gray with scattered brown sandstone partings.
725.0 - 725.2	Sandstone, brown, shaly.
725.2 - 726.0	Limestone, grayish brown, slightly sandy.
726.0 - 728.9	Sandstone and shale, brown and gray, laminated.
728.9 - 730.0	Sandstone, brown, shaly with scattered shale and mica partings.
730.0 - 732.0	Shale, gray with widely scattered brown sandstone partings.
732.0 - 732.4	Sandstone, brown, shaly.
732.4 - 732.7	Shale, gray.
732.7 - 733.0	Sandstone and shale, brown and gray, laminated.
733.0 - 735.0	Shale, gray with widely scattered brown sandstone partings.
735.0 - 740.7	Shale, gray.

UPPER BARTLESVILLE SANDSTONE

800.0 - 800.4	Sandstone, light brown with scattered mica partings.
800.4 - 806.0	Sandstone and shale, light brown and gray, laminated.
806.0 - 807.5	Shale, gray.
807.5 - 808.3	Shale, gray with scattered brown sandstone partings.

RECEIVED  
STATE CORPORATE COMMISSION

JAN 27 1988

TECH DIVISION  
CONSULTING  
Wichita, Kansas

LOGCompany Kelt Oil & Gas Lease Folger Well No. KCAF-10UPPER BARTLESVILLE SANDSTONE (Continued)

<u>Depth Interval, Feet</u>	<u>Description</u>
808.3 - 809.0	Sandstone, light brown with scattered shale and mica partings.
809.0 - 810.4	Sandstone and shale, light brown and gray, laminated.
810.4 - 811.0	Shale, gray, silty.
811.0 - 812.8	Sandstone, light brown with scattered shale and mica partings.
812.8 - 813.1	Sandstone and shale, light brown and gray, laminated.
813.1 - 818.1	Sandstone, light brown with scattered shale and mica partings.
818.1 - 819.1	Shale, gray with scattered angular light gray sandstone partings.
819.1 - 821.0	Sandstone, light brown with scattered shale and mica partings.
821.0 - 823.0	Sandstone, light brown.
823.0 - 825.0	Sandstone, light brown, slightly calcareous.
825.0 - 825.5	Sandstone, light brown with scattered shale nodules.
825.5 - 827.3	Shale, gray, silty.
827.3 - 828.3	Sandstone, light brown with scattered shale and mica partings.
828.3 - 828.8	Sandstone and shale, brown and gray, laminated.
828.8 - 829.1	Shale, gray, silty.
829.1 - 829.5	Shale and sandstone, gray and light brown, alternate layers.
829.5 - 830.2	Sandstone, light brown with scattered shale and mica partings.

LOG

Company Kelt Oil & Gas Lease Folger Well No. KCAF-10

UPPER BARTLESVILLE SANDSTONE (Continued)

<u>Depth Interval,</u> <u>Feet</u>	<u>Description</u>
830.2 - 831.2	Shale, gray with scattered light brown sandstone partings.
831.2 - 834.3	Shale and sandstone, gray and brown, laminated.
834.3 - 838.7	Shale, gray with scattered light brown sandstone partings.
838.7 - 840.0	Sandstone and shale, light brown and gray, laminated.