

LOGCompany Kelt Oil & Gas, Inc. Lease Umbarger Well No. KCU-2SQUIRREL SANDSTONE

<u>Depth Interval, Feet</u>	<u>Description</u>
672.5 - 674.7	Sandstone, light grayish brown, shaly with scattered shale partings.
674.7 - 679.0	Sandstone, dark brown with widely scattered shale and mica partings.
679.0 - 681.0	Sandstone, dark brown with scattered shale and mica partings.
681.0 - 683.3	Sandstone, grayish brown, slightly shaly with scattered shale and mica partings.
683.3 - 687.6	Sandstone, grayish brown, very shaly.
687.6 - 690.1	Shale, gray with scattered brown sandstone inclusions.

LOWER BARTLESVILLE SANDSTONE

941.0 - 941.4	Sandstone, brown with scattered shale partings.
941.4 - 942.3	Sandstone and shale, brown and gray, laminated.
942.3 - 942.8	Shale and sandstone, gray and light gray, laminated.
942.8 - 943.7	Sandstone and shale, brown and gray, laminated.
943.7 - 944.7	Shale, gray with scattered light gray sandstone partings.
944.7 - 945.5	Sandstone and shale, brown and gray, laminated.
945.5 - 945.9	Sandstone, brownish black, shaly, slightly carbonaceous with scattered shale and mica partings.
945.9 - 949.1	Shale and sandstone, gray and brown, laminated.
949.1 - 950.2	Shale, gray with scattered light gray sandstone partings.

RECEIVED
STATE CORPORATIONS COMMISSION

JAN 27 1988

CONSERVATION DIVISION
Wanda, Mica
Kansas

LOGCompany Kelt Oil & Gas, Inc. Lease Umbarger Well No. KCU-2LOWER BARTLESVILLE SANDSTONE (Continued)

<u>Depth Interval, Feet</u>	<u>Description</u>
950.2 - 951.7	Shale and sandstone, gray and brown, laminated.
951.7 - 954.2	Shale, gray.
954.2 - 954.8	Sandstone, grayish brown, very shaly.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1988

CONSERVATION DIVISION
Wichita, Kansas