

Company - JOHN C. JENSEN ET AL
Farm - John Hancock Ins.Co. No. 4.


SEC. 2
S Ec NW

T. 24

R. 15 E

Total Depth. 1557'3"
Comm. 11-16-44 Comp. 12-8-44
Shot or Treated.
Contractor. Oak Drlg.Co.
Issued. 4-21-45

County. Woodson
KANSAS



Elevation. _____

Production. Dry

CASING:

10" 22'5" P
8 1/2" 807' P

Figures Indicate Bottom of Formations.

soil & clay	10	lime hd	1552'3"
lime shells	18	lime	1557'3"
shale	72	Total Depth	
lime	76		
shale sdy	115	Top Of Miss. lime	1495SLM
lime shale lgt	144		
lime	148		
shale	150		
lime	155		
shale lgt	190		
lime	192		
shale	333		
lime	333		
shale	402		
lime	628		
shale lgt	633		
shale red	647		
shale blue	668		
lime	670		
shale lgt	677		
lime	746		
shale	750		
lime	773		
shale	777		
lime S.L.M.	802		
shale	926		
lime	929		
shale sdy	940		
lime	960		
shale	978		
shale sdy	1005		
lime	1019		
shale	1022		
lime	1039		
shale	1049		
lime	1060		
shale	1065		
lime	1105		
shale dk	1110		
shale lgt	1155		
Vernon sand, oil show	1165		
shale	1205		
sand ~ shale	1230		
shale sdy	1320		
shale dk	1330		
shale lgt	1495		
lime sdy	1505'6"		
flint & chert	1510 1/2"		
Reduced hole 1510 1/2" from			
8 1/2" to 6 5/8"			
lime hd	1516'0"		
some dolomite, oil show	1519'4"		
some dolomite no free			
oil	1522'9"		
lime hd	1525'7"		
lime show some gas	1528'3"		
lime? inc. oil show	1532'5"		
lime softer	1535'11"		
lime coarse	1538'8"		
lime drilled sft	1546'2"		