


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - JOHN C. JENSEN ET AL  
Farm - John Hancock Ins.Co. No. 5

SEC. 2 T. 24 R. 15 E  
NW NE NW

Total Depth. 1543'  
Comm. 1-8-45 Comp. 1-23-45  
Shot or Treated.  
Contractor. L. M. McCormick  
Issued. 3-3-45

County. Woodson  
KANSAS



CASING:  
10" 21'  
8 1/4" 791'

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.  
6 5/8" not set, drilled  
in 8 1/4" hole

soil	6
lime	8
clay	10
shale	135
lime	155
shale	333
lime	385
shale	403
lime	615
shale lgt	618
shale red	622
shale lgt	630
lime	640
shale	660
lime	789
shale	935
lime	940
shale	955
lime	975
shale	995
lime shells	1003
lime hrd	1006
shale	1032
lime	1065
shale	1075
lime	1085
shale	1090
lime	1095
lime shells	1115
shale	1118
sand gas(vernion)	1125
shale	1491 SIC

lime gy & sdy	1494
lime hrd lgt	1497
lime hrd & blue	
to flinty	1500
lime flint or	
chert(first gas	
& smell oil)	1503
lime flint or chert	
coarse more gas	1504 1/2
lime flint or chert	
coarse more gas	1507
lime gy hrd	1510
lime lgt & hrd	1530
lime chert'y cut	
good	1536
lime lighter	1539
some inc, in oil	
lime lighter	1543
Total Depth.	

no wtr showing other  
than the wtr from  
around 1100'