

1-16-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS, INC.
Farm- Legleiter No. 1

SEC. 1 T. 16 R. 18W
SW SW SW

Total Depth. 3544'
Comm. 2-12-60 Comp. 3-5-60
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 6-4-60

County Rush
KANSAS



Elevation. 1982 BB

Production. Dry

CASING:

8 5/8" 1130' cem. w/450 sx.
4 1/2" 3542' cem. w/75 sx.

Figures Indicate Bottom of Formations.

clay & rock	75
shale & shells	500
shale	530
sand	750
shale, shells & red bed	895
shale & red bed	1015
red bed	1120
anhydrite	1160
red bed, shale & shells	1515
shale & shells	2150
shale w/lime strks.	2245
lime & shale	3275
lime	3532
lime & chert	3544RTD
Total Depth	

TOPS:

Heebner	3215
Toronto	3234
Lansing-Kansas City	3265
Arbuckle.	3539

DST #1	3238-3275
DST #2	3298-3312
DST #3	3312-3322
DST #4	3424-3438
DST #5	3541-3544