


GUY D. HARPER-ORVIL DUNCAN
 Freeburg, No. 1

SEC 3 T. 24 R. 15 E.
 NEc SE

Total Depth, 1543
 Com. 5-27-38 Comp. 6-8-38
 Shot or Treated.
 Contractor.
 Issued. 9-10-38

County Woodson



CASING.

8 1/2" 772' UR 795
 65/8" 1498'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

soil	2	lime white	1125
yellow clay	7	shale dark	1135
lime	12	sand brown	1142
shale	15	shale dark	1225
shale white	45	shale light	1270
shale blue	350	shale dark	1496
lime white	365	lime grey	1501 ¹ / ₂
shale blue	375	lime brown	1506 ³ / ₄
lime white	398	lime grey	1511 ¹ / ₂
shale blue	415	lime chalky	1518
lime broken	630	lime	1525
red bed	640	lime sdy brown	1537
shale blue	660	lime grey	1543
lime	742	Total Depth.	
shale blk	745		
lime	768	HFV 590-610	
shale blue	775	HFV 775-793	
lime	793	4 BW 1086-1096	
shale blue	795	show oil at 1135-1142	
lime	800	show oil 1501-1506	
shale white	850	water 1511-1518	
shale dark	915	show oil and gas 1525-1529	
shale light	944	Plug and all casing pulled.	
lime grey	952		
shale light	975		
lime	987		
shale	1010		
lime	1012		
shale dark	1040		
lime hard & G.	1055		
shale	1070		
lime	1075		
shale blk	1086		
lime	1096		
shale	1109		
lime	1118		
shale blk	1122		