

DRILLER'S WELL LOG

DATE COMMENCED: 3-27-78
DATE COMPLETED: 4-6-78

L & L Oil Operations
J. Legleiter #1
S/2 NE/4 Sec. 11-16-18W
Rush County, Kansas

ELEVATION: 2000' K.B.
1997' D.F.
1995' G.L.

FORMATION DATA

1124'	Shale and Sand
1127-1162'	Anhydrite
1167-3230'	Shale and Lime
3230-3235'	Shale
3235-3247'	Lime
3247-3279'	Lime
3279-3505'	Lime
3505-3517'	Lime and Shale
3517-3555'	Shale, Lime, Chert and Sand
3555-3570'	Dolomite
3570-3575'	Dolomite
3575'	RTD

Anhydrite	1124	+ 876
Heebner	3230	-1230
Toronto	3247	-1247
Lansing	3279	-1279
Base Kansas City	3505	-1505
Conglomerate	3517	-1517
Rework Arbuckle	3555	-1555
Arbuckle	3570	-1570
RTD	3575	-1575

MAY 04 1978
OBSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE: Ran 28 Jts. New 24#
8 5/8" Casing. Tally 1127. Set @
1133' w/300 sks. 50-50 Pozmix and
150 sks. Common, 2% Gel, 3% c.c.
By Sun Cementing. P.D. @ 7:30 p.m.
Did Circulate.

PRODUCTION PIPE:
Set 3574' - 5 1/2" w/200 sks. Common
Cement. By Sun Cementing.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

DALE L. SMITH, of lawful age, does swear and state that the facts
and statements herein contained are true and correct to the best of his
knowledge.

Dale Smith