

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

13-16-18W

Company - IRON DRUG. CO.

Farm - Herrman

No. 1

SEC. 13

T. 16

R. 18 W

NWc NW

Total Depth. 3579'

Comm. 12-18-46

Comp. 1-10-47


Shot or Treated.

Contractor.

County. Rush

KANSAS

Issued. 2-15-47



CASING:

8 5/8" 1137' Cem. w/600 sx.

Elevation. 2007'nd set

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	0-19
post rock & shale	158
shale	300
shale & shells	495
sand	758
sand & shale	807
sand	841
shale	845
shale & shells	855
shale	960
red bed	1025
red bed & shells	1125
lime & shells	1135
anhydrite	1162
red bed & shale	1355
shale & shells	1570
shale	1800
lime	1865
shale & shells	1900
lime	1965
lime & shale	2025
lime	2120
lime brkn	2205
lime	2240
lime & shale	2280
lime brkn	2537
shale	2565
lime brkn	2600
lime & shale	2770
shale	2968
lime	2979
shale	2995
lime	3087
lime & shale	3195
lime	3260
shale	3273
lime	3530
shale & lime	3545
cherty conglomerate	3568
sand	3579
Total Depth.	

Tops:	
Heebner	3241
Lansing	3310
ZBC	3545
Arbuck's	3568

No oil string - dry hole