

15-009-75029

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


10-19-15W

Company - TRANSWESTERN OIL CO.
Farm - Seeber No. 1

SEC. 10 T. 19 R. 15 W
NW SW SW

Total Depth. 3589'
Comm. 4-16-44 Comp. 6-28-44
Shot or Treated.
Contractor. Mouser Drlg. Co.
Issued. 7-29-44

County. Barton
KANSAS



CASING:
8" 914'
5 1/2" 3570'

Elevation. _____

Production. Pot. 80 B.

Figures Indicate Bottom of Formations.

surface clay	150
shale sdy	200
sh. w/L shells	240
sand	250
sh w/L shells	465
sand	495
sh w/L shells	660
redbed	870
anhydrite	960
shale	1170
sh. w/L strks	1390
salt	1650
anhydrite	1670
lime	1760
shale	1810
lime	1850
lime w/sh brks	1963
lime	1980
lime & shale	2015
lime	2040
lime & shale	2260
lime	2304
shale	2325
lime	2374
lime & shale	2620
lime	2800
brkm l.	2845
lime	2896
sh w/L strks	2965
lime	3201
shale	3262
lime	3500
shale	3510
lime	3516
red shale	3530
conglomerate	3568
sand	3576
dolomite sdy	3583
sand	3589
Total Depth.	

Tops:

Lansing	3262
Congl	3530
Sand	3568
Arbuckle	3576

sh oil 3570-76
sh oil 3583-86