

20-16-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BAY PETROLEUM, STRAIN DRIG. & BUFFALO OIL SEC. 20 T. 16 R. 18W
Farm. Dechant No. 1 SE SE SE

Total Depth. 3581
Comm. 1-28-54 Comp. 2-12-54
Shot or Treated.
Contractor.
Issued. 6-12-54

County Rush

KANSAS



Elevation. 2000 RB

Production. dry

CASING:

10 3/4" 163' cem. w/135 sx

Figures Indicate Bottom of Formations.

All measurements R.B.

shale, soil & sand	30
post rock & shale	123
shale	173
shale & shells	550
sand	823
shale & shells	875
shale, redbed	1083
redbed & shale	1159
Anhydrite	1202
shale & shells	1390
lime & shale	1640
salt & shale	1810
lime & shale	1965
lime	2010
lime & shale	2160
lime	2455
lime & shale	2970
lime	3581
Total depth	

BHP 1145# IFI 50#
FFP 205#

3422-50, tool open 1 hr, weak
blow for 1 hr, rec. 1144' watery.
mud 20 mins. BHP 775#
3572-77, tool open 2 hrs. strong
blow thru test. Gas to surface
in 22 mins. rec. 30' mud - 30 mins.
BHP 1100#

Scout Tops:

Toronto	3242
Lansing	3274
Base Kansas City	3503
Conglomerate	3545
Reagon	3568
Granite	3583

DST 3135-70, open 1 hr. 10 mins. rec.
10' rotary mud 15 min. BHP 1050

3278-3301, Tool open 1 hr. rec.
90' muddy salt water 20 mins.
BHP 1060#.
3306-30, tool open 1 hr, weak
blow for 4 mins. rec. 5' rotary
mud 20 mins. BHP 0#

3333-80, tool open 1 hr, rec.
350' watery mud 20 mins.

Notary Public
 1974
 Notary Public