


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock Wichita, Kansas

Company - FRENCH & WINTERSCHIED
 Farm - Birk No. 7

SEC. 5 T. 24 S. 14E
 CW/2 E/2 NE
 750' W. of E.L. 1150' N.
 of S.L. of NE/4
 County. Woodson

KANSAS



Total Depth. 1702
 Comm. 6-10-51 Comp. 7-11-51
 Shot or Treated.
 Contractor.
 Issued. 7-28-51

Elevation. _____

Production. 2 BO

CASING:
 8" 37' cem. w/30 sx
 4 1/2" 1683' cem. w/30 sx (ground level)

Figures Indicate Bottom of Formations.

surface soil & clay	40
lime	41
shale & lime shells	133
lime	163
shale	565
lime	1055
shale	1170
lime	1200
shale & shells	1280
shale	1680
lime	1687

top of miss. lime 1680
 rotary table top
 correct to ground level 1676'
 bottom of rotary hole G.L. 1683'
 6-25-51 moved in tail in machine
 cleaned hole and drilled all
 cement hard lime to 1686'
 1686 to 1688' odor of oil
 1688 to 1690' softer inc. oil
 1690 to 1691 soft.
 washed clean
 Next morn- about 10 gal. oil.
 Drilled 1' nice brown & more oil
 Drilled 2' little brn much wht
 Drilled to 1696' same- lots of wht
 Drilled to 1698 1/2' -better lgt brn
 some more oil-washed clean
 Drilled to 1702' in lgt brown lime-
 much wht cuttings.
 Pump natural - 30 days later approx.
 2 bbls. oil.
 Total Depth 1702
 Scout Tops:
 ... Miss. 1680