

*Edminster  
oil*



*Ind  
1-16-20W*

WATSON #8  
NE SE SW  
Sec. 1-16S-20W  
Rush County, Kansas

Contractor: H-30, Inc.  
Geologist: Perry Hand

Elevation: 2090 GL; 2095 KB  
Prospect: Weitzel #346

- 2-20-84 MIRT. SPUD @ 5:00 p.m.
- 2-21-84 Ran 31 joints new 8-5/8", 24# surface casing, set @ 1307' with 275 sacks 60/40 pozmix, 3% calcium, 2% gel and 200 sacks common cement, 3% calcium, 2% gel. Cement did circulate. Plug down at 4:15 p.m.
- 2-22-84 Drilling @ 1340'.
- 2-23-84 Drilling @ 2580'.
- 2-24-84 Drilling @ 3310'.
- 2-25-84 Drill Stem Test #1 (3395-3460)  
Open 30", Shut In 30", Open 60", Shut In 30"  
Died in 14". Recovered 40' mud. No show of oil.  
IFP 92-92, ISIP 525, FFP 92-92, FSIP 371
- 2-26-84 Drill Stem Test #2 (3480-3580)  
Open 30", Shut In 30", Open 60", Shut In 30"  
Recovered 90' muddy water, oil specks in tool.  
IFP 92-103, ISIP 946, FFP 103-126, FSIP 785
- 2-27-84 Drill Stem Test #3 (3698-3742') Granite Wash  
Open 30", Shut In 30", Open 60", Shut In 30".  
Recovered 15' mud.  
IFP 92-92, ISIP 148, FFP 92-92, FSIP 114  
RTD 3807' Log was not run.  
Dry and Abandoned

SAMPLE TOPS:

Anhydrite	1304(+791)
Base Anhydrite	1346(+749)
Heebner	3353(-1258)
Lansing	3393(-1298)
Base Kansas City	3645(-1550)
Marmaton	3680(-1585)
Granite Wash	3735(-1640)
RTD	3807(-1712)