

JUN 29 1969

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

BULLOCK #1

NW NW NE Section 4-16S-20W

Rush County, Kansas

Commenced: April 13, 1969

Completed: April 26, 1969

*Sp: oil
Elev. 2212' KR*

OPERATOR - E. K. Edmiston Drilling Co., Inc.

DEPTH	FORMATION	REMARKS
From	To	
0	200	Surface clay and shale
		Ran 5 joints of 8-5/8" casing, set @ 200' w/150 sacks cement.
200	700	Shale and shells
700	920	Shale, shells and sand
920	1050	Sand
1050	1258	Shale
1258	1445	Shale and red bed
1445	1452	Shale
1452	1492	Anhydrite
1492	1930	Shale
1930	2080	Shale and shells
2080	3560	Lime and shale
3560	3797	Lime
3797	3876	Lime and chert
3876	3950	Lime
3950	4000	Conglomerate
4000	TD	
		Ran 117 joints of 5-1/2" casing, set @ 3698' w/90 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NW NE Section 4-16S-20W, Rush County, Kansas to the best of my knowledge and belief.

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 29 day of April, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.