

Sec. 5, T. 24 S., R. 14 S. +
 Farm No. **6801**
 Company
 Elev. T. D.
 Log No.

OKLAHOMA PRODUCING & REFINING CORPORATION
 STEVENSON WELL #7
 Sec. 5., T. 24 S., R. 14 S.
 Woodson County, Kansas.


Commenced Drilling Aug. 15, 1922.

Completed Drilling Sept. 2, 1922.

Initial Production-20 Bbls. after shot.

CASING RECORD.

10"	32'
8 1/4"	1165'
6-5/8"	1691'



FORMATION	TOP	BOTTOM
Soil	0	- 6
Clay	6	- 12
Lime, white hard	12	- 16
Shale, light		142
Lime, white hard		150
Shale, gray		200
Lime, shelly		220
Shale, grey		230
Lime, white hard		240
Shale, gray		300
Sand 4 1/2 B.W.		320
Shale, gray		386
Lime, white hard		415
Shale, gray		557
(Big lime at 557')		
Lime, white hard		773
Sand H.F.W.		785
Lime, white hard		830
Shale, dark		842
Lime, white hard		847
Shale, dark		852
Red rock		857
Shale, gray		875
Lime, white gritty		880
Lime, white hard		950
Shale, dark		955
Lime, white hard		975
Shale, dark		977
Lime, white hard		1022
Shale, dark		1135
Lime, white hard		1140
Shale, dark sandy		1150
Shale, dark		1164
Lime, white hard		1169
Shale, gray		1190
Lime, white hard		1225

FORMATION	TOP	BOTTOM
Shale, blue	1225	1250
Lime, white hard		1255
Shale, dark		1295
Lime, white hard		1520
Shale, dark		1325
Lime, white hard		1343
Shale, dark		1420
Lime, white hard		1425
Shale, dark		1445
Shale, gray		1455
Shale, dark		1625
Sand, gray		1640
Shale, gray		1690
1691 Ft. of 6-5/8" csg.		
Lime, white hard-Mississippi.		1704
Oil sand, soft		1719
Lime, white hard		1720

PI No.
 Year well
 & well A