

State Geological Survey
WICHITA BRANCH

14-16-20W

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE

RAM PETROLEUM CORP.
KAW Drilling Co., Inc.
MYERS "B" #1
SW/4 SE/4 NE/4 Section 14-16-20W
Rush County, Kansas
June 8, 1981
June 15, 1981

0	1545	Sand, Shale & Shell
1546	2142	Shale & Shell
2143	3518	Shale
3519	3895	Lime & Shale
	3895	R.T.D.

Spud hole at 10:30 a.m. on June 8, 1981. Drilled 341 feet of 12¼ inch hole. Ran 8 joints of new 8 5/8 inch, 24 pound casing. (Tallied at 326 feet.) Set at 339 feet with 225 sacks of common cement, 2% Gel, 3% C.C. Job complete at 3:15 p.m. on June 8, 1981.

Total Depth 3895'. Ran 97 joints of 4½ inch, 9½ pound new longstring casing. (Tallied at 3895'.) Set at 4 feet off bottom at 3891 feet with 175 sacks of 50/50 pos. mix, 2% Gel. Cement by Sun Cementing. Job complete at 10:30 a.m. on June 15, 1981.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I, K. S. Martin, President of KAW Drilling Co., Inc., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


K. S. Martin, President