

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- PURE OIL CO.
Farm- Stevenson, H.D. No. 11

SEC. 5 T. 24 R. 11E
Approx. C NE NW
1980' E of WL 610' S of NL

Total Depth. 1738'

Comm. 3-27-57


Comp. 4-4-57

County Woodson
KANSAS

Shot or Treated.

Contractor. Barnard Drlg. Co. & Endicott Oil Field Service. Co.

Issued. 10-18-58



CASING:

8 5/8" 81' w/65 sx cem.
5 1/2" 1738' w/150 sx cem.

Elevation. 1199' DF

Production. 56 BO

All Meas. fr RB 1' above DF. Figures Indicate Bottom of Formations.

surface soil, shale 20 Perf; 4/8/57 5 1/2" 1698-1712'
lime 25 w/56 shots.

shale 40
lime 50 Acid Record: 4/9/57 1698-1712'
shale 60 w/3000 gals.

lime, brkn 82 Ran Bird Well Survey.

shale 125

lime 140

shale 190

lime 195

shale 200

lime 225

shale 240

lime 260

shale 310

lime 318

shale 390

lime 400

lime, shale 490

shale 560

lime 630

lime, wtr sand 645

lime 775

shale 845

lime, shale 900

lime 1030

shale, shells 1090

shale, sdy 1110

shale, shells 1140

lime 1155

shale, lime 1180

lime 1250

lime, shale 1305

lime(see core record starting @ 1305') 1315

shale 1323

lime 1325

shale 1326

lime 1329

shale 1330

lime, shale 1500

shale 1685

coal 1686

shale 1687

siltstone 1688

chert 1690

lime, cherty 1691

sand 1694

shale 1697

dolomite 1738

Total Depth

TOPS:

Mississippi lime 1688

PAY ZONE:

1698-1712'