

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


10-19-15W

Company - HELMERICH & PAYNE, INC.
 Farm - Seeber "B" No. 2

SEC. 10 T. 19 R. 15 W
 NW NE SW

Total Depth. 3549
 Comm. 1-27-45 Comp. 3-22-45
 Shot or Treated.
 Contractor.
 Issued. 5-19-45

County. Barton
 KANSAS



CASING:
 10 3/4" 899' Cem.
 5 1/2" 3536' Cem.

Elevation. _____

Production. Min. Well

Figures Indicate Bottom of Formations.

red bed & surface soil	0-165
shale & shells	280
shale sdy	300
shale & shells	350
sand Dakota	410
lime shells	450
Dakota Sand	515
red bed & shale	660
shells, shale	680
red bed & shells	810
shale & shells	898
anhydrite	940
lime	955
sand	1060
red shale	1090
shale & shells	1142
sand	1180
shale & shells	1220
shale	1365
shale & shells	1640
lime	1725
lime sdy	2020
lime	2635
sand, Ft. Riley w/lime	
streaks	2710
sand, lime & shale	2770
lime & shale	2912
lime Topeka	2954
lime	3056
lime & chert	3120
lime	3490
conglomerate	3535
conglomerate & sand	3538
Reagan sand	3542
sand hrd	3547
sand hrd wh	3549
Total Depth	
Tops:	
Lansing-Kans. City	3240
Sandy Conglomerate	3496
Cherty Conglomerate	3508
Reagan Sand	3530
Rotary total depth	3541