

OPERATOR:
 CONTRACTOR:
 WELL NAME:
 LOCATION:

SEP 8 0 REC'D
 State Geological Survey
 WICHITA, BRANCH

Martin Oil Company
 KAW Drilling Co., Inc.
 Myers #1
 SW NW NW, Section 24-16S-20W
 Rush County, Kansas
 July 3, 1980
 July 9, 1980

SPUD DATE:
 COMPLETION DATE:

0	265	Sand, Shale & Shells
265	1117	Shale, Sand & Red Beds
1117	1369	Shale
1369	1404	Anhydrite
1404	2165	Shale
2165	2375	Shale & Lime
2375	2599	Shale
2599	3560	Shale & Lime
3560	3755	Lime
3755	3830	Lime & Shale
3830	3862	Lime
	3862	R.T.D.

Drilled 266' of 12 1/4" hole. Ran 6 jts. of new 8 5/8" - 23# (8rd - range 3) casing. (Talley 252') Set @ 265' K.B. with 175 sx. of 60/40 posmix, 2% gel, 3% Ca.Cl. Cement did circulate. Plug was down at 4:00 p.m. 7/03/80.

T.D. 3862', ran 95 jts. of 5 1/2" - 15 1/2# (8rd - range 3) new casing. (Talley 3837.17') Set @ 3851' K.B. with 100 sx. of RFC cement. Plug was down at 11:15 p.m. 7-09-80. Cement by Dowell.

STATE OF KANSAS)
) §S
 COUNTY OF SEDGWICK)

I, K.S. Martin, President of KAW Drilling Co., Inc., being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

K.S. Martin
 K.S. Martin, President

SUBSCRIBED AND SWORN to before me on this 14th day of July, 1980.