

30-16-20W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- D. R. LAUCK OIL CO.
Farm- Irvin No. 2

SEC. 30 T. 16 R. 20W
NW SW SW

Total Depth. 4126'
Comm. 9-30-60 Comp. 10-11-60
Shot or Treated.
Contractor.
Issued. 11-26-60

County Rush

KANSAS



CASING:
8 5/8" 273' cem w/170 sx.

Elevation. 2188' DF

Production. Dry

Figures indicate Bottom of Formations.

surface clay	45
sand	55
shale	720
sand	730
shale & shells	820
red bed	850
sand	860
red bed	880
sand	915
red bed & sand strks	1165
red bed	1465
Anhydrite	1500
red bed, shale & shells	1665
shale & shells	2200
shale & lime	2560
lime & shale	2655
shale & lime	2770
shale & shells	2885
shale & lime	3290
chalky lime & shale	3410
lime & shale	3470
lime broken	3560
Heebner shale	3564
lime & shale	3575
shale & lime	3602
lime	3859
lime & shale	3905
cherty shale & lime	3944
shale	3952
lime	4001
lime & shale	4040
shale	4047
sand	4052
sand & shale	4075
Arbuckle	4126 RTD
Total Depth	

Base Kansas City	3872
Ft. Scott	3948
Cherokee Shale	4012
Cherokee Sand	4026
Cherty Conglomerate	4073
Arbuckle	4108

DST #1 4036-4062', op 1 hr; fair blow
1 hr, rec. 540' muddy water, IFP 90#,
FFP 255#, BHP 800#/20 mins.

TOPS:	WELEX
Heebner	3557
Toronto	3572
Lansing	3600