

31-16-20W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WELCH & OLSSON DRIG. CO., INC.
Farm- North No. 1

SEC. 31 T. 16 R. 20W
SE SE NE

Total Depth. 4110'

Comm. 5-22-56

Comp. 6-3-56

Shot or Treated.


Contractor. Welch & Olsson Drig. Co., Inc.

Issued. 7-14-56

County

Rush

KANSAS



CASING:

8 /58" 221.5.' w/175 sx cem.

Elevation. 2168 RB

Production. Dry

Figures Indicate Bottom of Formations.

surface soil-shale	150
shale	850
sand	1100
shale-shells-red bed	1295
shale-shells	1425
Anhydrite	1460
shale-shells-red bed	1655
shale-shells	2110
shale-shells w/lime str.	
	2220
shale w/lime stks	2310
lime-shale	2575
shale-shells w/few lime	
stls	2650
shale-lime	2790
shale-shells	2840
lime-shale	2885
shale w/lime strks	3045
shale-lime	3150
lime-shale	3575
lime	3775
lime-shale w/stks chert	3820
lime	3910
lime-shale-chert	3950
lime-chert	3970
cherty lime	3985
shale-lime-sand	4020
lime-chert-shale-sand	4032
chert-shale	4045
lime-chert-shale	4061
Conglomerate	4095
lime	4110
Total Depth	

TOPS:

Heebner	3536
Toronto	3556
Lansing-Kansas City	3577
B/Kansas City	3846
Cherokee shale	3985
Arbuckle	4078