

1-28-17E

Al Prosser Well #2

Neosho County
Sec 1, Twp 28S, Rg 17E
NW of water well

11-22-49 to 1-27-50

Driller: John Mitchell
R. M. Willis
Contractor: Reuben Willis

11' 8 $\frac{1}{4}$ " casing
383' 6 $\frac{1}{4}$ "
680' 4 7/8"

15	soil & clay	15		10	dark shale	785
24	shale	39		34	shale	819
55	water sand	94	hole full of water	1	sand-oil smell	820
61	shale	155		5	bkn sand-oilshow	825
20	sandy shells	175		20	dark shale	845
72	lime	247		2	slate	847 Puff gas
2	shale	249		33	white shale	880 12,500
4	slate	253		20	dark shale	900
4	lime	257		29	sdv shale	929
4	shale	261		2	bkn sand-oil smell	931
8	sdv lime	269		4	sand - oil show	935
16	shale	285		5	sand	940 puff gas
25	lime	310		6	sand - oil show	946
1	shale	311		3	sand - lighter	949
4	slate	315		5	sand - light	954
45	lime	360		5	sand	959
16	shale	376			Making water - plugged back to 950'	
5	slate	381				
19	shale	400				
10	shells	410				
14	sdv shale	424				
12	shale	436				
4	slate	440	gas bubbles			
11	lime	451				
4	shells	455				
28	lime	483				
2	shale	485				
27	sdv shale	512				
14	shale	526				
12	sdv shale	538				
13	shale	551				
40	lime	591				
39	shale	630				
20	lime	650				
10	slate	660	hole full of water'			
5	lime	665				
15	white shale	680	4 7/8 (poor casing spot)			
72	shale	752				
2	lime	754				
7	shale	761				
1	lime	762				
13	white shale	775	casing spot if REAM?			