

32-16-29W
NW-SW-NW

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

Beren Corporation
Abercrombie Drilling, Inc.
Dickey #1
NW SW NW, Section 32-16S-28W²⁹
Lane County, Kansas
October 13, 1978
October 22, 1978

State Geological Survey
WICHITA BRANCH
JUL 8 0 RECD

0	280	Sand, Shale & Post Rock
280	1220	Sand & Shale
1220	2028	Sand & Shale
2028	2233	Sand, Shale & Red bed
2233	2265	Anhydrite
2265	2580	Shale & Shells
2580	2755	Shale & Shells
2755	2980	Shale & Lime
2980	3191	Shale & Lime
3191	3415	Shale & Lime
3415	3610	Shale & Lime
3610	3777	Shale & Lime
3777	3950	Lime & Shale
3950	4063	Lime & Shale
4063	4178	Lime & Shale
4178	4278	Shale & Lime
4278	4360	Shale & Lime
4360	4378	Shale & Lime
4378	4404	Lime
4404	4425	Lime
4425	4434	Shale & Lime
4434	4485	Lime
4485	4530	Lime
4530	4537	Lime
4537	4581	Lime
	4581	Rotary Total Depth

Spud hole at 6:45 p.m., October 13, 1978. Drilled 280' of 12 1/4" hole. Ran 6 joints of 8 5/8" - 28# casing. Set at 276.35' with 200 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:00 midnite on October 13, 1978.

T.D. 4581'. Set 1st plug at 1200' with 70 sacks, 2nd plug at 250' with 20 sacks, 3rd plug at 40' with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:30 a.m. on October 22, 1978.

SAMPLE TOPS:

Anhydrite 2233'
B/Anhydrite 2265'