

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 133 — 21,357
County Number

Operator

L. F. Kepley

Address

4226 Gold, Wichita, Ks. 67217

Well No.

71

Lease Name

Kepley

Footage Location

252

feet from (N) (S) line

448

feet from (E) (W) line

Principal Contractor

Allison Oil Co. Inc.

Geologist

none

Spud Date

12-1-80

Date Completed

Total Depth

832

P.B.T.D.

Directional Deviation


12-9-80

Oil and/or Gas Purchaser

Square Deal Oil CoS. 2 T. 28 R. 17ELoc. 252 NSL 448' EWLCounty NEOSHO

640 Acres

N



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
<u>Surface</u>	<u>7"</u>	<u>6"</u>	<u>8.5</u>	<u>45'</u>	<u>Portland</u>	<u>7</u>	
<u>Casing</u>	<u>5 1/4"</u>	<u>27/8</u>	<u>6.5</u>	<u>751</u>	<u>Portland</u>	<u>87</u>	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			<u>3</u>	<u>22.7 gram</u>	<u>8</u>
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
<u>Gel Water</u>	<u>690.5 to 698.5</u>

INITIAL PRODUCTION

Date of first production <u>12-19-80</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pump</u>				
RATE OF PRODUCTION PER 24 HOURS	Oil <u>1/2</u> bbls.	Gas _____ bbls.	Water <u>4</u> bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator L. F. Kepley		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 11	Lease Name Kepley	Oil
SEC 12 T 28 R 17 E SW 1/4		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil and Clay	0	12		
Shale	12	27		
Lime	27	37		
Shale	37	168	Top KC	168
Lime	168	241		
Shale and slate	241	245		
Lime	245	251		
Shale	251	290		
Lime	290	297		
Shale	297	304		
Lime	304	313		
Shale and Slate	313	319	Bottom KC	355
Lime	319	355		
Shale	355	438		
Lime	438	450		
Shale	450	465		
Lime	465	476		
Shale	476	559		
Lime	559	562	40 Foot	
Slate and shale	562	568		
Lime	568	597		
Shale	597	633		
Lime	633	650	20 Foot	
Shale	650	658		
Lime	658	664	5 Foot	
Shale Dark	664	670		
Shale Lite	670	684		
Lime	684	689		
Oil Sand	689	700		
Broken Sand	700	705	Squirrel	111
Shale	705	754		
Lime	754	756		
Shale	756	832	TD	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature Title Date
---------------	---