

WICHITA BRANCH

KANSAS DRILLERS LOG

IMPORTANT
Kansas State Survey request
submitted on this well.


15-165-2066

S. 35 T. 16 R. 20 ^RW

Loc. NENE SW

County Rush

640 Acres
N



Locate well correctly

Elev.: Gr. 2107'

DF 2110' KB 2112'

API No. 15 — 165 — 20,665
County Number

Operator
Jinkins Oil Co., Inc.

Address
Suite 411, 200 East First Wichita, Kansas 67202

Well No. #1 Lease Name Weltmer

Footage Location
330 feet from (N) line 330 feet from (E) line

Principal Contractor Emphasis Oil Operations Geologist Robert B. Jinkins

Spud Date 11-14-77 Total Depth 3925 P.B.T.D.

Date Completed 11-23-77 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	260'	Common	150	3% cc, 2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas bbls. Water MCF Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody
is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas
66044.

Operator **Jinkins Oil Company, Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: **Dry Hole**

Well No. **1** Lease Name **Weltmer**

S 35 T 16S R 20 ^{Ex}_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface clay and sand	0	70		
Shale and shells	70	455	Anhydrite	1345
Shale	455	710	Topeka	3156
Sand and shale	710	1345	Heebner	3457
Anhydrite	1345	1380	Lansing	3504
Shale	1380	2250	BKC	3766
Shale and lime	2250	2675	Marmaton	3808
Lime and shale	2675	3323	Pawnee	3818
Lime	3323	3357	Conglomerate	3869
Shale and Lime	3357	3563	Arbuckle	3890
Lime and shale	3563	3726	Total Depth	3925
Lime	3726	3830		
Lime and shale	3830	3900	Electra, Inc.	Radiation-
Lime	3900	3925	Accurlog	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Robert B. Jinkins</i>
	Signature
	President
	Title
	11-29-77
	Date