

SUPERIOR TESTERS
RR #1, Box 295B, Great Bend, Kansas

10-16-20W

Date 8-7-84 Location NE 10-16-20 Elevation _____ County Rush
Company CARLILE Drilling Company Number of Copies 5
Address 901 OIL & GAS Building Fort Worth TEXAS 76102
Charts Mailed to 901 OIL & GAS Building Fort Worth TEXAS 76102
Invoice Mailed to 901 OIL & GAS Building Fortworth TEXAS 76102
Lease bullock Well No. 1 Formation Tested Cherokee Test No. 1
Depth 3925 Tested from 3891 to 3925 Packer Size 6 3/4 Anchor Length 34
Top Packer Depth 3886 ft. Bottom Packer Depth 3891 ft. Dual Packers YES
Tool Joint Size 4 1/2" F.H. Tool Size 5 5/8" D.D. Hole Size 7 7/8 Did Packer Hold YES
Drilling Contractor B & B Drilling Rig #2
Length Drill Pipe 3862 I.D. Drill Pipe 3.80 Tool Joint Size 4 1/2" F.H.
Length Weight Pipe NONE I.D. Weight Pipe NONE Tool Joint Size NONE
Length Drill Collars NONE I.D. Drill Collars NONE Tool Joint Size NONE

Tool Open I.F.P. from 2:45 p.m. to 3:15 p.m. 30 min
Tool Closed I.C.I.P. from 3:15 p.m. to 4:00 p.m. 45 min
Tool Open F.F.P. from 4:00 p.m. to 5:00 p.m. 60 min
Tool Closed F.C.I.P. from 5:00 p.m. to 6:30 p.m. 90 min

from [B] <u>64</u> P.S.I. to [C] <u>73</u> P.S.I.
[D] <u>1107</u> P.S.I.
from [E] <u>73</u> P.S.I. to [F] <u>92</u> P.S.I.
[G] <u>1063</u> P.S.I.

Initial Hydrostatic Pressure [A] 2195 P.S.I. Final Hydrostatic Pressure [H] 2146 P.S.I. Maximum Temp 113 °F
Initial Blow WEAK blow died in 18 min. then weak intermittent throughout
Final Blow WEAK BLOW
Gas to Surface NONE Min. Oil to Surface NONE Min. Mut Weight 10" Viscosity 44
Gas Guaged NONE

STATE CORPORATION COMMISSION

NOV 15 1984

CONSERVATION DIVISION

Wichita, Kansas

Recovery 90 Feet of watery mud with specks of oil

STATE CORPORATION COMMISSION

NOV 15 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks SEND Everything to HERMAN FEILHOTTER Box 86
INSURANCE \$40.00 PLAINVILLE KANSAS 67663

Extra Equipment-Jars 300.00 Safety Joint 60.00 Extra Packer NONE Straddle NONE Hook Wall NONE
Top Recorder No. 13561 Clock no. 27813 Depth 3919 Cir. Sub NONE Sampler NONE
Bottom Recorder No. 5463 Clock No. 9096 Depth 3922 Chlorides - pits 65,000 D.S.T. _____

Price of Job \$1,000.00
Tool Operator Gene Budig
Approved By Paul Montfort

SUPERIOR TESTERS, INC. SHALL NOT BE LIABLE FOR DAMAGE OF ANY KIND TO THE PROPERTY OR PERSONEL OF THE ONE FOR WHOM A TEST IS MADE, OF FOR ANY LOSS SUFFERED OR SUSTAINED, DIRECTLY OR INDIRECTLY, THROUGH THE USE OF ITS EQUIPMENT, OR ITS STATEMENTS OR OPINION CONCERNING THE RESULTS OF ANY TEST. TOOLS LOST OR DAMAGED IN THE HOLE SHALL BE PAID FOR AT COST BY THE PARTY FOR WHOM THE TEST IS MADE.

Ticket No 9813