


WOODSON PIPELINE & PROD.CO.
Winterschoid No. 10

SEC. 6 T. 24 R. 14E.
NE NW SW SE

Total Depth 1713
Comm. 3-10-38. Comp. 4-7-38
Shot or Treated. 2500 gal.
Contractor. Keas Drlg. Co.
Issued. 5-21-38

County Woodson.



CASING.

12" 8 ft
10" 792'
8" 1202'
65/8" 1674'

Elevation.

Production. 93 B.

Figures Indicate Bottom of Formations.

soil	2	shale	1155
clay	7	lime	1157
lime shells	17	shale	1165
shale	20	lime	1180
red rock	30	shale	1185
lime	33	lime	1190
shale	45	sand	1199
lime	48	shale	1203 Steel line Meas. 1202
shale	115	lime	1205
lime	117	shale	1222
shale	128	lime	1225
lime	131	shale	1235
shale	136	lime	1240
lime	139	shale	1245
shale	171	lime	1250
lime	175	shale	1255
shale	180	lime	1265
lime	185	shale	1267
shale	210	lime	1277
lime	220	shale	1282
shale	235	lime	1284
lime	238	shale	1289
shale	360	lime	1293
lime	365	shale	1302
shale	370	lime	1306
lime	375	shale	1350
shale	535	lime	1353
lime	760	shale	1400
water sand	785	lime	1404
Hole full wtr	765	shale	1415
steel line Meas.	792	shale	1671 Bad cave 1615 ft.
lime	810	Miss lime	1690 Steel line Meas. 1674
shale	815	brown lime	1694 show of oil 1690-1694
lime	820	lime grey sdy	1701 good show at 1701
shale	824	brown sdy lime	1713
lime	826	Total Depth.	
red rock	831		
shale	850		
lime	935		
Gas	925		
shale D.	940		
lime	993		
shale	1140		
lime	1145		