

OKLAHOMA PRODUCING & REFINING CORPORATION

J. WINTERSCHIED #8

Sec. 6., T. 24 S., R. 14 E.

200' s. and 200' W.

from NE corner.

Sec. Two, R.R. No.

Perm. No. 6815

Elev. T. D.

Log No.

Drilling commenced 11-30-22

Drilling completed 12-28-22

TOTAL DEPTH 1739'

Small gas well - rock pressure 260#.

CASING RECORD.

10"	330' pull-
8 1/4"	1150'
6-5/8"	1689' pull-
5-3/16"	1568'
12 1/2"	320' pull-

Shot record:- Shot 1-11-23 by Independent Torpedo Company, between 1550 and 1562, with 40 qts., 12' of 5 1/2" shell; packer set at 1540' 8 1/2" Robinson disk, on 1-14-23.

FORMATION TOP BOTTOM

Soil, black soft	0	-	5
Clay, yellow soft	5	-	10
Shale, blue soft	10	-	50
Lime, white hard			55
Shale, blue			115
Lime, white hard			120
Shale, blue			135
Lime, white hard			140
Shale, blue			180
Lime, white hard			184
Shale, dark			189
Lime white hard			197
Shale, gray			210
Lime, white hard			228
Shale, gray			240
Lime, white hard			245
Shale sandy gray			280
Sand white soft			300
Show of gas 285.			
H.F.W. 290'			
Shale, gray			370
Lime, white hard			375
Shale, gray			380
Lime, white hard			385
Shale, gray			545
H.F.W.		---	780
Lime, white hard	545		830
Shale, blue			837
Lime, white hard			841
Rock red soft			843
Shale, gray			865
Lime, white hard			1000
Shale, gray			1120
Lime, white hard			1125
Shale, gray			1168
Lime, white hard			1201
Shale gray			1236

We got 2 ft. of oil sand from 1734 to 1736, very little oil; plugged back to gas sand at 1555'.

FORMATION TOP BOTTOM

Lime, white hard	1236	1246
Shale, gray		1256
Lime, white hard		1271
Shale, gray		1281
Lime, white hard		1293
Shale, gray		1306
Lime white hard		1316
Shale, gray		1350
Lime, white hard		1355
Shale, gray		1375
Shale, dark		1385
Shale, gray		1476
Shale, dark		1501
Shale, gray		1555
Sand, gas white soft		1560
show of gas 1555.		
Sand white hard		1660
H.F.W. 1603.		
Shale dark		1677
Lime sandy white hard		1681
Lime Mississippi, white hd.		1734
Sandy lime		1736
Show oil		
Sand, white		1739
showed some water.		

TOTAL DEPTH 1739'

P.B. to 1562. and shot for 100,000
gas. - produced less than one year -
then abandoned.