

4-26-16w

file

~~4-16-16w~~

file

STERLING DRILLING COMPANY
P. O. BOX 129
Sterling, Kansas 67579

WELL LOG - - - - - HAYHER "A" 93-4
Located: 330' F&L; 330' FWL, S/2 Lot 2, Section 4-26-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 18, 1981
COMPLETED: January 26, 1981

TOTAL DEPTH: 4550'

AUG 30 1988
KANSAS CONSERVATION COMMISSION
WICHITA BRANCH

L&C

- 0 - 230 Sand
- 230 - 448 Sand and Shale
- 448 - 1053 Shale
- 1053 - 1068 anhydrite
- 1068 - 1540 shale and Lime Stringer
- 1540 - 3940 Lime and shale
- 3940 - 4110 Lime
- 4110 - 4245 Lime and Shale
- 4245 - 4419 Lime
- 4419 - 4550 Lime and shale

CASING RECORD

Ran 11 joints 8 5/8", 28" OD casing.
434' pipe set at 445' K.B. Cemented
with 400 sacks 60/40 Pozmix with 3% cc.
Plug down at 9:15 PM, 1-18-81, by Howco.

Ran 141 joints 4 1/2", 10.5" OD casing.
4537.77' pipe set at 4545' K.B. Cemented
with 100 sacks Howco Lite, followed with
125 sacks Pozmix, 18% salt, 20 bbl. salt
flush ahead, 3/4 of 1% CFR-2, 1/8" floccle,
1/8" tuffiber, 5" gilsonite per sack.
Plug down at 11:30 AM, 1-26-81, by Howco.

RECEIVED
CONSERVATION COMMISSION

AUG 29 1988

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 3/4° at 2050'
2° at 4245'