

Pratt

W-11 No. 11

Bucklin

Survey

1

Elev. 1755 K.B.

NE

Rig #1

50% - Chicago Group

40% - G. M.R. Oil

10% - Wm. Graham Oil Co.

V. Hess-Geol.

Rocket Drlg. 3-1279

Tidewater Assoc. Oil Co.

P.O. Box 731, Tulsa, Okla.

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

330

Ft. from S. Line

Ft. from W. Line

330

Ft. from E. Line


Date	Depth	
11-8-53		13 3/8" @ 175' W/190 sx. cem. 2 gel. 4cc.
11-9		Drlg. Cem.
		Plugged down at 11:30 A.M. 11-9-53)
11-10	430	Drlg
11-10	575	Anhy (1180)
11-11	1600	Losing Circulation (to run 8 5/8)

713949

Date	Depth	
11-12	1900	8 5/8" @ 702' W/100 sx. cem.
11-12	232	2 C.C. *Plugged down @
11-12	230	5:15 P.M. 11-11-53
11-13	1878	Drlg
11-16	3243	Drlg
11-17	3600	Circ. - waiting on Vernon
11-18	3630	Is. (-1875)
11-18	3733	Drlg.
11-19	3841	Drlg
11-20	3432	Heeb. (-1677)
11-20	3460	Dg. Sd. (-1705)
	3611	Br. Im. (-1856)
	3935	Drlg.
11-21	4023	Drlg
11-23	4210	Drlg
11-23	4095	Miss (-2340)
	4185	Kinderhook (-2430)
	4225	Drlg.
11-24	4291	Viola (-2536)
	4308	Drlg.
11-25	4325	Drlg.
		D.S.T. #1 4298-4318 - op.
		cl 15".
		1 hr./, Rec. 880' for oil
		(30' mdy wtr. Oil spray to
		surf 25"; gas to surf in 12"

- BHP 1260#

State Kansas County Pratt
 Company G.M.R. Oil Co. Well No. 1A
 Farm Bucklin
 Survey _____
 Block No. _____ Sec. 6 Twp. 28 Range 11W
 Co-Ord. _____ Elev. 1755 K.B.



Rig #1

(page 2)

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
11-27	4413	Drlg
		D.S.T. #2 4318-31 - op. 45"
		shut in 10", rec. 35' mud,
		BHP-440#
	4390	Simpson
		Trip 4390-4413
11-28	4446	Drlg
11-30	4527 R.T.D.	5 1/2 @ 4370 W/70 sacks cement
		Plug down @ 6:45 AM 11-30-53

Date	Depth	
12-8		L-W Log Drilling in
12-9		Perf. 4314-18 (12 ^s) baled 2 BOPH (10% Wtr) 500 A. Swbd 48 bbls fluid per hr. for 2 hours (30% Wtr)
12-19	Pump + fl 117	80 + 52 BW / 16 hr. 15 BWPH 33 BOPH
12-20	Pump + fl 213	80 + 22 BW / 24 hr. Gravity - 38° Putting on Pump
12-29	Start	Test: Pumped 194 BW / 24 hr, 4 Tests
		Crude Oil Purchaser Skelly Oil Co. Trucker - Feaster Chg 19¢ bbl. tr. chg.