


THE PURE OIL COMPANY.
 John Winterscheid No. 17

SEC 6 T. 24 R. 14E.
 SE NE SW
 1495' N of S.L. 2453' E of WL
 3819' S of N.L. 200' W of EL

Total Depth. 1717
 Comm. 5-18-36 Comp. 6-10-36
 Shot or Treated 2000 gal acid.
 Contractor.
 Issued. 7-18-36
 CASING.

County. Woodson.



12 1/2" 19'
 10" 960' Pulled.
 8 1/2" 1678'

Elevation.

Production. 133 B. after acid.

Figures Indicate Bottom of Formations.

clay	14	lime	1186
clay	41	shale	1237
lime	43	lime	1240
shale	54	shale	1242
lime	56	lime	1253
shale	74	lime and shale	1290
sdv shale	79	shale	1305
shale	107	lime	1310
sand	120	shale	1422
shale	125	lime	1427
sand	127	shale	1455
shale	135	sand	1460
lime and shale	145	shale	1496
shale	180	sdv shale grey	1505
lime	185	shale blk	1534
shale	190	shale grey	1548
lime shells	193	sand fine grey	1555
lime	195	shale blk	1578
shale	212	greenish grey pyritic shale	1590
lime	226	shale blk, streaks of sand	
shale	275	and coal	1670
sand	280	chert white	1676
lime	285	Top of Miss lime	1670
sdv shale	295	brown sugery dolomite some	
shale	370	chert	1717
lime	375	Total Depth.	
shale	378		
lime	381		
shale	546		
lime	554		
sand 6 BW	560		
lime	575		
sand	581		
shale	586		
lime	604		
shale	609		
lime	650		
shale	658		
lime	825		
shale	844		
rod rock	849		
shale	882		
lime	938		
shale	942		
lime	1006		
shale	1017		
sand	1038		
shale	1143		
lime	1150		
shale	1170		