

47974

THE PURE OIL COMPANY
John Winterscheid No. 18.

SEC 6 T. 24 R. 14E
NE SE SW
1057' N SL 2448' E WL
4257' S NL 2845' W EL
County. Woodson

Total Depth. 1724'
Comm. 6-15-36 Comp. 7-1-36
Shot or Treated. 3000 Gals. Acid. 1677-1724'
Contractor.
Issued. 8-22-36

CASING.
10 " 960' Pulled
6 5/8" 1677'



Elevation.

Production. 138 B. after
shot 1st 24 hr.

Figures Indicate Bottom of Formations.

soil	3	shale grey	1480
shale	10	lime	1482
lime	11	shale sdy	1500
clay yellow	30	black mic. shale	
shale	43	wf sand	1505
lime	45	black smooth shale	1540
shale	117	grey mic shale wf	
sand	127	streaks coal	1557
shale	132	dark grey mic shale	1637
sand	142	light grey very mic.	
shale	178	shale	1675
lime	183	black gran. shale	
shale	192	streaks coal	
lime	197	little sand	1677
shale	280	chert white & fine	
sand	285	medium round sand	1693
shale	370	brownish granular knotty	
lime	385	lime	1696
shale	550	brown granular sugary	
lime	586	dolomite with pcs of	
shale blk	589	white chert	1724
lime	605	Total Depth	
shale	610		
lime	651		
shale	659	Top Mississippi 1677'	
lime HFW 775	810		
shale	834		
red rock	842		
shale	885		
lime	939		
shale	949		
lime	965		
shale	970		
lime	995		
shale	998		
lime	1000		
sdv lime	1005		
shale	1015		
sand	1035		
shale	1145		
lime	1152		
shale	1170		
lime	1189		
shale	1230		
lime shell	1257		
shale	1266		
lime shell	1296		
lime	1305		
shale	1430		
sdv shale	1445		
shale	1450		