


THE STELBAR OIL CORP. ET AL.  
 Geo. G. Knapp No. 1

SEC. 23 T. 32 R. 3 E  
 C SW NW

Total Depth. 3485  
 Comn. 9-22-42 Comp. 10-11-42  
 Shot or Treated.  
 Contractor. E.B. Shawver.  
 Issued. 11-14-42

County Cowley



CASING.

10" 64'8"

Elevation.

Production. DRY

Figures Indicate Bottom of Formations,

surface clay	35
sand	55
shalo	65
limo	75
shalo and limo	140
rod rock	145
shalo	200
limo	390
rod rock	400
shalo and shells	530
rod rock	560
shale and shells	1295
limo	1465
shalo	1534
limo	1560
shalo and shells	2175
sand	2217
shalo	2320
sand	2331
shalo	2522
sand	2560
shalo	2610
sand	2620
shalo	2631
lime	2744
shalo	2755
lime	2765
shalo	2795
limo	2810
shalo	2839
shalo and limo	2878
shalo	3075
shalo sdy	3090
shalo	3107
limo	3247
shalo	3304
limo	3430
shalo	3460
sand Oil stain	3464
limo	3485
Total Depth.	

Layton sand 2522-2560  
 K.C. limo 2631-2744  
 Wilcox sand 3460-3464  
 Arbuckle lime 3464-3485

Odor of oil and gas from 2735-2740  
 spotted oil stain.  
 ran drill stem test 3469-81, no shows  
 water in core 3481-3485.