

34-16-21W

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**508 EAST MURDOCK - WICHITA, KANSAS**

COMPANY CHIEF DRILLING

SEC. 34 T. 16S. 21W

FARM Starrett

NO. 2

LOC. C NE SW

TOTAL DEPTH 4190'

COMM. 12-21-67


COMP. 1-3-68

SHOT OR TREATED

CONTRACTOR Chief Drilling

ISSUED 2-10-68

COUNTY Ness



CASING

20	10	
15	8	5/8" 285' cem w/ 175 sx
12	6	
13	5	

ELEVATION 2231' KB

PRODUCTION DRY/Miss

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand & Clay	0	705
Shale	705	720
Red Bed	720	920
Red Bed, Shale & Sand		
Streaks	920	1500
Shale & Shells	1500	1512
Anhydrite	1512	1551
Shale, Shells & Red Bed	1551	1920
Shale & Lime Streaks	1920	2182
Shale & Lime	2182	2537
Lime	2537	2743
Lime & Shale	2743	3320
Lime	3320	3615
Shale & Lime	3615	3654
Lime	3654	3942
Shale & Cherty Lime	3942	4016
Cherty Lime	4016	4085
Shale & Lime	4085	4115
Sand & Shale	4115	4163
Chert	4163	4190
Total Depth	4190	

2220' G.F.  
 2228 D.F.  
 2231 K.B.

FORMATION TOPS

LOG TOPS

Anhydrite (driller)	1512 + 719
Heebner	3614 -1383
Toronto	3633 -1402
Lansing	3654 -1423
Base Kansas City	3943 -1712
Pawnee	4016 -1785
Ft. Scott	4098 -1867
Cherokee Shale	4108 -1877
1st Sand	4115 -1884
Mississippi	4164 -1933
LOG T.D.	4189 -1958


DRY & ABANDONED

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE SW Section 34-16S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Thomas G. Wesselowski*  
 Thomas G. Wesselowski, Geologist



Subscribed and sworn to before me this 4th day of January, 1968.

*Carmen R. Cook*  
 Carmen R. Cook, Notary Public