

State Kansas County Russell

Company GMR Oil Co. Well No. 2

Farm Shafer

Survey

Block No. Sec. 26 Twp. 14 Range 13W

Co-Ord. Elev. 1706 KB

SE NE SE


1/3-Lohmann-Johnson  
1/3-GMR  
1/3-Wm. Graham

Continental Oil

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line Ft. from S. Line

Ft. from W. Line Ft. from E. Line

Date	Depth	Spd 10-26-52
		8 5/8" @ 208
10-28	1080	Drlg
10-29	1710	Drlg
10-30	2010	Drlg
10-31	2340	Drlg
11-1	2540	Drlg
	2835	Lansing (-1129)
DST 2871-2904, op 1 hr, wk bl. Rec 15'		
mud. No BHP		

Date	Depth	714396
11-3-52	2835	Lansing (-1129)
11-4	2177	Gran Haven Lime
	2182	Dry Shale Zone (1st Tarkio
		sand zone)
	2199	Dover Lime
	2206	Langdon Shale Zone (2nd Tar-
		kio Sand zone)
	2249	Tarkio Lime (-543)
	2270	Willard Shale Zone
	2321	Elmont Lime
	2623	Topeka Lime
	2761	Heebner
	2783	Toronto
	2835	Lansing (-1129)
	2920	R.T.D. 4½" @ 2918'
11-9	Perf 2209-20.	Swabbing. Washing
		down rest of day. Fraced
		with sand and oil.
11-12	Test 1 BWPH, 1/2 BOPH	
	Perf 2184-88 w/12 <sup>S</sup>	Mud above cem.
		Squeezed.
11-15	DOC	
	Perf 2184-88 w/12 <sup>S</sup>	

State Kansas County Russell


Company GMR Oil Co. Well No. 2

Farm Shafer

Survey \_\_\_\_\_

Block No. \_\_\_\_\_ Sec. 26 Twp. 14S Range 13W

Co-Ord. \_\_\_\_\_ Elev. 1706 KB  
SE NE SE



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
11-16		Swb 2 BFPH, 50% oil
11-17		Decr to $1\frac{1}{4}$ BFPH, $3/4$ oil.
		Oil fraced. 2000# pressure.
		Testing 1 BOPH. Continue to
		test.
11-19		Swabbed all nite. Will re-
		frac.
11-20		Swb $1\frac{1}{2}$ BOPH. Considerable in-
		crease in gas.

Date	Depth	714396
11-21		Decreased to less than 1/2 BO Will plug.
11-21		Shot off casing - Rec 1875' of 4 1/2".
		D&A
11-18		
11-19		