

STENCILED

NOV 23 1968

35-16-21W

WELL LOG

E.K. Edmiston Drilling Co., Inc.
First National Bank Building
Wichita, Kansas 67200

ZELLER "B" #1
C NW NW Section 35-16S-21W
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 10-14-68
Completed: 10-25-68

Casing Record: 8-5/8" set @ 328' w/185 sacks Common Sunset, 2% Gel

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u> 2227 K.B.
Clay	0	95	
Shale	95	329	
Shale & Sand	329	955	
Sand	955	1185	
Shale & Shells	1185	1499	
Anhydrite	1499	1534	
Shale, Shells and Sand Streaks	1534	1920	
Shale	1920	2185	
Shale & Lime	2185	3935	
Lime	3935	4025	
Lime, Shale & Sand	4025	4080	
Sand	4080	4117	
Lime & Chert	4117	4165	
Total Depth	4165		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NW NW Section 35-16S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Manager

Subscribed and sworn to before me this 30th day of October, 1968.

Carmen R. Cook
Carmen R. Cook, Notary Public



expires: Dec. 12, 1970