



WELL COMPLETION REPORT AND
DRILLER'S LOG


WICHITA BRANCH

API No. 15 — 135 — 22,008
County Number

S. 36 T. 16S R. 21 ^K_W

Loc. SE SE SE

County NESS



Locate well correctly
Elev.: Gr. 2170

DF 2172 KB 2175

Operator <u>White & Ellis Drilling, Inc.</u>			
Address <u>401 E. Douglas - Suite 500, Wichita, KS 67202</u>			
Well No. <u>#1</u>	Lease Name <u>HERDMAN</u>		
Footage Location <u>330</u> feet from (X) (S) line <u>330</u> feet from (E) (X) line			
Principal Contractor		Geologist <u>Micheal Dixon</u>	
Spud Date <u>6/1/81</u>	Date Completed <u>6/6/81</u>	Total Depth <u>4239'</u>	P.B.T.D.
Directional Deviation		Oil and/or Gas Purchaser	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"		508	60-40 poz	250	2% gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.) <u>D&A</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator White & Ellis Drilling, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name HERDMAN	21 Dry Hole
S <u>36</u> T <u>16</u> S <u>R</u> <u>21</u> <u>X</u> W		SE SE SE

WELL LOG			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner	3555	-1380		
Toronto	3575	-1400		
Lansing Kansas City	3600	-1425		
Base Kansas City	3882	-1707		
Marmaton	3948	-1773		
Cherokee Shale	4008	-1833		
Cherokee Sand	4042	-1867		
Conglomerate	4092	-1919		
Arbuckle	4178	-2003		
RTD	4239	-2064		
DST #1 4040-50'. 30-30-30-30. Fairly strong blow throughout. 570' SW, 65 PPM Chlorides. IFP 114-217 FFP 240-298 ISIP 898 FSIP 887				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	Bill Stout Geological Student 6/10/81
	Signature Title Date