

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PICKRELL DRILLING

SEC. 4 T. 16 R. 21W
LOC. C NW SW

FARM Elmore "J" NO. 1

TOTAL DEPTH 4348'

COMM. 7-23-67

COMP. 8-2-67



SHOT OR TREATED

CONTRACTOR Pickrell Drilling

ISSUED 10-14-67

COUNTY Ness

KANSAS



CASING

20	10	
15	8	5/8" 249' cem w/ 165 sx
12	6	
13	5 1/2"	4345' cem w/ 125 sx

ELEVATION 2374' KB

PRODUCTION 36 BOPD PLUS 2% W/
Chero 4252 Grav 38

FIGURES INDICATE BOTTOM OF FORMATIONS

70	Clay Post Rock
249	Grey Shale & Shells
1485	Shale & Lime
1608	Shale
1650	Lime & Shale
2385	Shale
2940	Lime & Shale
3260	Shale
3400	Shale & Sandy Lime
3676	Sandy Lime & Shale
4245	Lime & Shale
4310	Sand
4312	Lime & Shale
4347	Miss. Chert & Lime, R.T.D.
4348	L.T.D.

C. F. S.

4235
4245
4255
4265
4280
4300

Slope Tests

2500
3000
3500
4000

S. L. M.

None

TOPS: LOG

Anhydrite	1688
Heebner	3762
Lansing Kansas City	3804
Pawnee	4148
Cherokee	4210
1st sand	4234
2nd sand	4241
3rd sand	4251
4th sand	4282
5th sand	4292
Mississippi	4305

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY