

IMPORTANT
Kans. Geo. Survey request
samples on this well.

KANSAS DRILLERS LOG

API No. 15 — 135 — 21,734
County Number

Operator

Bankoff Oil Co.

Address

Drawer 2479 Tulsa, Okla 74101

Well No.

#1

Lease Name

Ryan

Footage Location

990

feet from (N) line

990

feet from (E) (W) line

Principal Contractor

DNB Drilling Company

Geologist

Donald Douglass

Spud Date

12/6/79

Total Depth

4373'

P.B.T.D.

Date Completed

12/16/79

Oil Purchaser


Bigheart Pipe Line

S. 6 T. 16 R. 21 W

Loc. SE NW SW

County Ness

640 Acres
N



Locate well correctly

Elev.: Gr. 2399

DF 2402 KB 2404

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 3/8"	28#	219'	common	150	60/40 pozmix 3% cc, 2% jel
Production		5 1/2"	14#	4372	Common	100	60/40 pozmix 10 sks salt flush

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		4287-4289 4293-4299
TUBING RECORD					
Size	Setting depth	Packer set at			
2" EUE	4275				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
none	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
1/15/80	pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	25 bbls.		MCF	bbls.	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Bankoff Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Ryan	Oil
S <u>6</u> T <u>16</u> R <u>21</u> ^{EX} _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1719	+ 683		
Base Anhydrite	1762	+ 640		
Heebner	3775	-1369		
Lansing	3817	-1411		
Pawnee	4165	-1759		
B. Pawnee	4232	-1826		
Fort Scott	4255	-1848		
Cherokee	4264	-1857		
1st Sand	4275	-1868		
2nd Sand	4283	-1882		
3rd Sand	4294	-1888		
Mississippi	4341	-1935		
TD	4373	-1955		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Co-Partner
	Title
	May 30, 1980
	Date