

Dep

IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 6 T. 16 R. 21 ^N _W
Loc. NW SE SW
County Ness

KANSAS DRILLERS LOG

API No. 15 — 135 County — 21,798 Number

Operator
Bankoff Oil Co.

Address
Drawer 2479 Tulsa, Okla 74101

Well No. #2 Lease Name Ryan


Footage Location
990 feet from (N) (S) line 940 feet from (E) (W) line

Principal Contractor DNB Drilling, Inc. Geologist Bob Douglass

Spud Date 5/10/80 Total Depth 4350 P.B.T.D.

Date Completed 5/16/80 Oil Purchaser SWD

State Geological Survey
WICHITA BRANCH
JUL 8 0 1980



Locate well correctly
Elev.: Gr. 2390
DF 2392 KB 2395

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	218'	Common	160	3% cc, 2% gel
Production		4 1/2"		1730	Common	200	60/40 pozmix

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		1330-1370

TUBING RECORD

Size 2" Setting depth 1239.25 Packer set at 1238

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Bankoff Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 2	Lease Name Ryan	SWD
S <u>6</u> T <u>16</u> R <u>21</u> ^X _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1708	+ 687		
B. Anhydrite	1750	+ 640		
Heebner	3763	-1368		
Lansing	3804	-1409		
Pawnee	4154	-1759		
B. Pawnee	4222	-1827		
Fort Scott	4244	-1849		
Cherokee Sh.	4254	-1859		
1st Sand	4264	-1869		
2nd Sand	4278	-1883		
3rd Sand	4286	-1891		
Mississippi	4338	-1943		
TD	4347	-1952		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Co-Partner Title
	7/2/80 Date