

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


1-32-4E

Company- STEWART OIL COMPANY
Farm- Defore-Roberts No. 5

SEC. 1 T. 32 R. 4E
NE SE NE

County Cowley
KANSAS

Total Depth. 3003'
Comm. 12-26-56 Comp. 12-31-56
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 2-16-57



Elevation. 1245' KB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

surface	120
lime & shale	500
shale	535
shale & lime	
stks	1160
sandy shale	1355
shale & lime	1445
sand & shale	1480
lime & shale	1903
lime	1906
sandy shale	1917
sand	1930
sand & shale	1970
shale & lime	2025
shale	2120
sandy shale	2140
shale & lime	
strks	2314
sand (Layton)	2349
shale & lime	2389
sand & shale	2434
lime (Kansas	
City)	2580
shale	2665
shale & lime	2735
lime	2785
lime & shale	2814
shale	2865
lime & shale	2880
shale	2908
sand (Bartle-	
sville)	2923
shale	3001
shale	3003
Total Depth	

SCOUT TOPS

Stalnaker	1887
Layton	2317
Kansas City	2435
Base/Kansas City	2581
Marmaton	2674
Oswego	2727
Cherokee	2796
Cattlemen Sand	2910