

DRILLERS LOG

State Geological Survey
WICHITA BRANCH

14-16-22W

JUNE #1
Ness County
SE NW SE
Sec. 14-16S-22W

Company: Beren Corporation

Contractor: Strata Drilling, A Division of BEREDCO INC.

Comm: October 12, 1981

Comp.: October 19, 1981

Casing: 8 jts. New 20#, 8-5/8" Set @ 322' w/200 sks 60-40 Pozmix, 2% gel, 3% CC. cement did circ. PD 8:25 P.M. 10/12/81. by Sun Cement.
108 jts. New 5 1/2" OHM 4403' set @ 4389' or 1' off bottom w/200 sks 60-40 Pozmix, 10% Salt 10# Gilsonite per sks. 2% Gel, 3/4 of 1% CFR2 20 Bbl. Salt Flush. Div Tool 1683' w/ 350 sks Halib. Light-50 sks Common. Job Comp. @ 11:45 A.M. 10-19-81 by Halliburton.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale, Lime & Sand	0'	475'
Shale & Sand	475'	1450'
Shale & Anhydrite	1450'	1875'
Shale	1875'	2400'
Lime & Shale	2400'	4390'

Total Footage Depth 4390'

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1981

STATE OF KANSAS

ss:

COUNTY OF SEDGWICK

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log as shown by the drilling reports.

BEREDCO

J. D. Marcus

Subscribed and sworn to before me this 21st day of October, 1981.



Cheryl L. Benoit