


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg. Wichita, Kansas

Company - C. W. DARLING et al  
Farm Wolf No. 2

SEC. 4 T. 24 R. 14E  
NE NE NE

Total Depth. 1657'  
Comm. 11-12-48 Comp. 11-29-48  
Shot or Treated. acidized 2/1500 gal  
Contractor. C. H. Barkor  
Issued. 1-1-49

County. Woodson  
KANSAS



CASING:  
10" 818' pulled 6 5/8" com w/25 sx  
8" 1225' pulled  
6 5/8" 1635'

Elevation. \_\_\_\_\_

Production. 50 bbl no water

soil	2
clay	20
lime shells	30
shale	70
lime	83
shale	153
lime	159
shale	165
lime	168
shale	180
red bed	190
shale	200
limo	208
shale	258
lime	272
shale	275
limo	280
shale	343
lime	356
shale	515
lime 3 BW 570-75	614
shale	617
lime	683
shale	685
limo	702
shale	705
limo	708
shale	710
lime HFW 740-45	777
shale	790
lime	805
shale	835
lime	845
shale	855
lime	907
sand	925
lime 4 BW 935-40	960
shale	1105
lime	1109
shale	1112
limo	1114
shale	1123
limo	1145
shale	1165
lime shells	1195
shale	1203
lime	1205
shale	1265
lime	1275
shale	1305
sand	1317
shale	1495
sand show of oil	1525
shalo	1630
limo Miss chatty	1635
limo brn	1643
limo	1647
lime chatty	1650
lime brn oil	1657
Total depth	

Figures Indicate Bottom of Formations.  
Hole filled up 200' from 8 pm  
till 9 am before acidizing.  
After acidizing pumped 50  
bbl daily.