

23-16-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WELCH & OLSSON DRILLING COMPANY, INC.
Farm- Walker No. I

SEC. 23 T. 16 R. 22W
NW NW SE

Total Depth. 4400'
Comm. 4-7-56 Comp. 4-22-56
Shot or Treated.
Contractor. Welch & Olsson Drilling Co. Inc.
Issued. 7-7-56

County Ness KANSAS



Elevation. 2390' R. B.

Production. 11 BOPD

CASING:

8 5/8" 225' cem. w/175 sx.

Figures indicate Bottom of Formations.

shale	925
false anhydrite	945
shale & shells w/ streaks	
of sand and red bed	1130
sand	1220
shale & shells	1450
red bed, shale & sand	1640
red bed & shale	1715
anhydrite w/pydrite	1745
shale, shells	2355
shale w/lime streaks	2670
shale & lime	2825
shale w/lime streaks	2910
lime & shale	2945
shale & shells	3060
shale w/lime streaks	3175
shale & lime	3300
sandy lime & shale	3425
lime & shale	3715
lime	4060
lime & chert.	4105
lime	4189
lime & shale	4225
lime	4280
lime & shale	4340
shale & lime	4373
shale & broken chert.	4390
chert.	4398
lime	4400
Total Depth	

TOPS:

heebner	3785
toronto	3808
lansing-kansas city	3822
base kansas city	4119
maraton	4132
cherokee shale	4267
cherokee sand	4341
mississippi	4380