

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


1-32-4E

Company- STEWART OIL COMPANY
Farm- Long "A" No. 3

SEC. 1 T. 32 R. 4E
NW NE NE

Total Depth. 3027
Comm. 1-10-57 Comp. 1-17-57
Shot or Treated.
Contractor. White & Ellis Drlg ,Inc.
Issued. 3-16-57

County Cowley
KANSAS



CASING:
8 5/8" 121' cem w/89 sx.
5 1/2" 2953' cem w/100 sx.

Elevation. 1215

Production. 47 BOPD

Kelly bushing measurements 5' above ground level. Figures indicate Bottom of Formations.

soil	10
lime HD	69
shale sandy	77
lime hd	82
shale drk	87
lime broken	104
red rock	108
lime	121
lime, shale	220
lime	300
lime, shale	555
shale, shells	805
shale, lime	960
lime	970
shale sandy	1050
lime	1060
shale, lime	1070
shale, shells	1160
lime w/shale strks	1320
lime	1350
shale (stickly)	1395
lime, shale	1540
shale, shells	1600
lime, shale	1660
shale, shells	1865
sand, shale	1980
shale	2060
sand, shale	2075
shale	2084
lime	2110
shale, shells	2277
sand	2283
sand, shale	2385
lime	2525
shale, lime	2595
shale, shells	2635
shale, lime	2700
lime broken	2755
shale sandy	2858
sand	2879
shale sandy	2943
sand	2960
shale, lime	3016
lime	3027

Total Depth

Tops:
Stalnaker (Scout) 1851
Layton (") 2277
Kansas City 2385
Cattlesman Sand
(Scout) 2862
Bartlesville sand
(Scout) 2936
Miss. 3016