


1-32-4E

Company. The TEXAS COMPANY  
 Farm. Blanch R. Morris No. 1

SEC. 1 T. 32 R. 4E  
 NW NE SE

Total Depth. 3095 PB 3058  
 Comm. 6-14-56 Comp. 6-28-56  
 Shot or Treated.  
 Contractor. Earl F. Wakefield  
 Issued. 8-4-56

County Cowley  
 KANSAS



Elevation. 1240 DF

Production. Pumping 45 BO & no water

CASING:

10 3/4" 120' cem w/125 sx. Circ.  
 7" 3092' cem w/100 sx.

Figures indicate Bottom of Formations.

lime	195
red rock	210
lime, shale strks	525
shale, lime, shells	563
shale	870
lime, shale	1120
shale	1200
shale, lime	1350
shale	1360
lime, shale	1438
shale	1470
lime, shale	1635
lime	1740
shale, lime strks	1900
lime (Itan)	1910
sand (Stalnaker)	1944
shale	1967
shale, lime strks	1981
shale sdy	2016
shale, lime strks	2110
sand	2118
shale, lime strks	2322
sand (Layton)	2339
shale	2391
sand	2415
shale	2438
lime (Kansas City)	2515
lime w/shale brks	2610
shale sdy	2625
shale	2706
lime (Oswego)	2718
shale, lime	2775
lime	2795
shale, lime	2869
lime	2885
shale	2896
sand, shale	2908
sand (Bartlesville)	2922
shale	2985
sand	2996
shale	3020
shale w/ S lime stks	3039
shale cherty	3045
lime (Miss.) RTD	3095
Total Depth	
PB to 3058	

Tops:

Layton	2325
Kansas City	2437
Base K. C.	2577
Cherokee	2786
Skinner sand	2907
Mississippi	3040