

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


1-32-4E

Company- STEWART OIL CO.  
Farm-Long "A" No. 6

SEC. 1 T. 32 R. 4E  
NE NE NE

Total Depth. 2370'  
Comm. 7-5-57 Comp. 7-6-57  
Shot or Treated.  
Contractor. White & Ellis Drlg., Inc.  
Issued. 9-21-57

County Cowley  
KANSAS



Elevation. 1252' RB

Production. 27 BOPD

CASING:

8 5/8" 127' w/100 sx cem.  
5 1/2" 2369' w/150 sx cem.

Figures indicate Bottom of Formations.

KB Meas. 5' above GL.  
soil 7  
lime 42  
lime brkn 127  
lime 150  
lime-red rock strks 220  
lime-shale 310  
shale-lime strks 420  
lime-shale strks 590  
sand 610  
shale-shells 850  
shale-lime 970  
sand 990  
sdy shale-shells 1060  
lime 1115  
lime-shells 1170  
sand (shly.) 1195  
lime 1230  
lime-shale 1470  
lime 1580  
lime-shale 1670  
sdy shales-shells 1823  
sand-shale 1876  
lime 1889  
sand-shale 2030  
shale-shell 2088  
shale-sdy shale 2140  
shale-shell 2303  
sand-show oil 2323  
sand-shale 2370  
Total Depth

Perf. 2315-2139 - 4 jets per ft.

TOPS:  
Stalnaker (scout) 1876  
Layton 2303