


8

State Kansas County Sheridan
 Company G.M.R Oil Well No. 1
 Farm Ernigh
 Survey _____

Block No. _____ Sec. 4 Twp. 7 Range 29W

Co-Ord. _____ Elev. (2805) D/F

new new re *Rig #3 (2808 R/B)*
 Geol. - B. Fractory
 10% - Wm. Graham Oil Co
 40% - G.M.R Oil Co.
 50% - Chicago
 *3000. Westpan Hydrocarbon
 *2250. Magnolia



NOTE: Show Sketch of Lease and Well Location in Above Space

330 Ft. from N. Line Ft. from S. Line
330 Ft. from W. Line Ft. from E. Line

Date	Depth	Spd.
1953		6-7-53
		8 5/8 @ 280' w / 200' x
		3 c.c.'s
6-9-53	1425	Orlg.
6-12	3445	
	3713	stop (-905)
6-14	3904-10	Abw. (-1096) 3905(-1097)
	3910-14	Leavenworth (-1102)
	3929-38	
	3944	Land. - 1136 3947(-1139)
	3950	Orlg.

6-15-D.S.T. #1-3973-4000' - rec. 60' mud
 ops 30" @ 20"
 WK. bl. Dent in 13" B.N.P. - 0

714854

Date	Depth	
D.S.T. # 1	3998. 2 - 4020	op 1 hr., wk. blow, Rec 6" rec. 30' mud w/ few
sl. tr. of oil skin)	4095	specks of oil BHP 40 ⁺ Wintered Lime (-1297)
D.S.T. # 3	4095	4115 - op 1 hr., ^{20"} very wk. blow for 2" - then level rec. 4' mud specked
5-16--	4157 B.K.C. 4157	Only ahead
5-18	4380	
	4451	Miss Chert (-1643)
	4485	" Lime (-1667)
	4488	TD
D.S.T.	4454-88	op 1 hr. Cl 20"
		V. wk Blow - dead in 2"
		Rec 30' Muddy Wtr.
		BHP 1000 [#] F.I. Pr 0 [#]
		Hydratetic Pr 2300 [#]
	4488 R.I.D.	Rans Sq.
6-20		5 1/2" @ 4157 w/ 75 sq
		W.O.C.T.
6-29		M.I.C.T.
6-30	Perf. 4108-06	- w/ 3 ^s per ft. s.o.
		500 acid
		1300 [#] pres. - No brk. for 7 hrs.
		sub. 5 gophy
		1 gophy Q+Q