


Total Depth: 1691
Comm. 6-15-35 Comp. 7-9-35
Shot or Treated.
Contractor: The Shull Drilling Co.
Issued. 8-24-35

County. Woodson.



CASING.

10" 760' 8 1/4" 1145'
UR 790 .65/8" 1608'

Elevation.

Production. 10 bbls.,

Figures Indicate Bottom of Formations

soil and clay	15	shale white	1140
lime	20	lime	1145
shale	30	lime	1155
lime	45	lime sdy	1185
shale	90	shale	1200
lime	95	shale and lime shells	1260
shale grey	110	water encountered from 1185-1200	3BPH
lime grey	120	bailed hole dry.	
shale white	140	lime	1295
shale white	150	shale	1335
lime	170	lime broken	1345
shale	185	shale	1450
lime	205	shale	1550
shale	225	lime sdy	1570
lime	235	sand	1595
shale	275	shale	1615
shale grey	340	water encountered from 1570-1585	
lime	365	Hole full	
shale	385	shale dark	1608
shale	415	shale	1645
shale	475	lime	1683
shale	525	oil show brown	1683
lime	555	sand	1691
lime	610	Total Depth.	
lime	615		
water encountered 560'	4BPH		
Bad hole Filling up & Drilling out.			
lime	650		
filling up and drilling out.			
lime	745		
Water encountered 735	HF		
lime	760		
lime	770		
lime	780		
lime	790		
shale	795		
shale	810		
red rock blue	815		
shale	850		
lime	865		
lime	975		
shale	1015		
shale grey	1090		
shale	1115		
lime	1120		