

D R I L L E R S L O G

#4 Baer

CASING RECORD:
9 jts. new 20#
8-5/8" surface
casing

COMPANY: Beren Corporation
CONTRACTOR: Strata Drilling Company
COMMENCED: March 18, 1981
COMPLETED: March 25, 1981

DESCRIPTION: S/2 S/2
Section 16-16S-23W
Ness County, Kansas

ELEVATION: 2455' GL

TOTAL ROTARY
DEPTH: 4446'

FORMATION

FROM

TO

REMARKS

Surface soil, sale, lime
Shale, sand, shale
Anhydrite
Shale
Lime and shale

0 345
345 1782
1782 1817
1817 2660
2660 4446

Ran 334' new 20# 8-5/8" surface cas-
ing; set and cemented at 339' with
250 sacks 60-40 pozmix, 3% C.C.
Cement circulated. Plug down at
9:45 p.m., March 18, 1981.

Ran 3 drill stem tests.

Ran 1 electric log.

Ran 99 jts. new 4½" casing, set and
cemented at 4445' with 200 sacks
60-40 pozmix, 10% salt, 2% gel.
Plug down at 5:00 p.m., March 25,
1981.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to
the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp